

SECTION 01457 - TESTING AND INSPECTION BY OWNER

PART 1 GENERAL

1.1 SUMMARY

A. Section Includes:

1. Administrative and procedural requirements for Owner provided testing and inspection services.

B. Related Requirements:

1. Construction Contract Between Walmart and Contractor: Inspections, testing, and approvals required by public authorities. Contractor obligations to perform work in accordance with Contract Documents.
2. Section 01452 – Contractor Quality Control: Administrative and procedural requirements for Contractor quality assurance and quality control.
3. Section 01770 - Contract Closeout: Project Record Documents.
4. Appendix B - Testing, Inspection, and Observation by Owner:
 - a. Architect-Engineer Site Observation: Site observation by Owner's Architect and Engineer Consultants.
 - b. Civil Engineering Consultant Site Observation: Site observation by Owner's Civil Engineering Consultant.
 - c. Owner furnished Construction Laboratory (CTL) tests and inspections.

- C. General requirements for testing and inspection to be performed by the Contractor is specified in Section 01452.

1.2 OWNER RESPONSIBILITIES

- A. Employment and payment for services of a Construction Testing Laboratory (CTL) and/or Special Inspector (SI) to perform specified testing and inspecting will be by the Owner under separate contract except for specified testing required to be selected and paid for by the Contractor as may be required by individual specification sections.

1.3 CONTRACTOR RESPONSIBILITIES

- A. Cooperate with CTL/SI personnel, and provide access to the Work and to manufacturer's facilities.
- B. Provide incidental labor and facilities to provide access to Work to be tested, to obtain and handle samples at the site or at source of products to be tested, to facilitate tests and inspections, and to provide storage and curing of test samples. Provide lift equipment as required for inspection personnel of the Owner or the Owner's representatives.
- C. Provide CTL 24 hour notice prior to expected time for operations requiring inspecting and testing services.
- D. Notify in writing the Walmart Construction Manager three working days prior to expected time for operations requiring inspecting and testing services.
- E. Provide the CTL/SI with access to the internet for the purpose of logging deviations onto the Walmart Observation Log on the Walmart Building Portal website.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

END OF SECTION