SECTION 15600 - REFRIGERATION SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

- A. Owner's Refrigeration equipment supplier will furnish refrigeration equipment as indicated on Drawings and defined Appendix A Products and Work by Owner or Separate Contractor.
 - 1. Obtain services of a Walmart approved Refrigeration Contractor to perform all work in this Section, unless noted otherwise.
- B. Section Includes:
 - 1. Work and responsibilities associated with owner furnished refrigeration equipment for installation by the Contractor. Description of work and responsibilities includes, but is not limited to, installation, start-up, and commissioning of refrigeration systems and display cases, evaporator coils, condensers or condenser/compressor units, and interconnecting piping, condensate drains, and field installed refrigeration controls.
 - 2. Work and responsibilities for refrigeration equipment related items provided by the Contractor, including minor items necessary to the installation which may not specifically be mentioned in the Contract Documents. Such items include, but are not limited to, screws, shims, anchors, escutcheons, brackets, pipe sleeves, sealants, flux, glue, and changes due to unforeseen obstructions.
- C. Related Requirements:
- D. Work shall mean complete installation of equipment and devices in accordance with applicable Specifications and as described in the Drawings, Application Sheets, Manufacturer's Legend Sheets and Instructions.
- E. Refrigeration Contractor shall mean the General Contractor's, Walmart approved, Subcontractor that is responsible for performing the refrigeration work as specified on the construction documents. Refrigeration Contractor shall be responsible for compliance with applicable codes, ordinances, and work permits.
- F. Refrigeration Equipment: Equipment shown or noted on the Drawings to include the following:
 - 1. Hot cases.
 - 2. Cold cases.
 - 3. Freezer/Cooler Panels and Doors.
 - 4. Evaporators.
 - 5. Mini-Racks.
 - 6. Rack-in Box (RIB).
 - 7. Separate Condensers.
 - 8. Refrigerated Case Protection (specified in Section 10260).
 - 9. Floor Mounted Railings (Section 05500).
 - 10. Other related equipment not specifically listed.

1.2 REFERENCES

- A. The publications listed below form a part of this specification to the extent referenced. Publications are referenced within the text by the basic designation only.
- B. ASTM International (ASTM):
 - 1. ASTM A 536 Ductile Iron Castings.
 - 2. ASTM B 75 Seamless Copper Tube.
 - 3. ASTM B 280 Seamless Copper Tube for Air Conditioning and Refrigeration Field Service.
 - 4. ASTM B 584 Copper Alloy Sand Castings for General Applications.
 - 5. ASTM B 813 Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube.
 - 6. ASTM C 1710 Installation of Flexible Closed Cell Preformed Insulation in Tube and Sheet Form.

- 7. ASTM D 2665 Polyvinyl Chloride (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings.
- 8. ASTM D 2564 Solvent Cements for Polyvinyl Chloride (PVC) Plastic Pipe and Fittings.
- 9. ASTM E 84 Surface Burning Characteristics of Building Materials.
- C. American National Standards (ANSI):
 1. ANSI B 16.22 Wrought Copper Alloy Solder Joint Pressure Fittings.

1.3 CLOSEOUT SUBMITTALS

- A. Comply with the requirements of Section 01770.
- B. Refrigeration Installation Handover Document / Sign Off Sheet: Submit completed Refrigeration Installation Handover Document / Sign Off Sheet to Walmart Stores, Inc., 2001 SE 10th Street, Bentonville AR 72712-0550, Attention: Mechanical Construction Manager
- C. Record Documents: Provide laminated half-size refrigeration and energy management as-built drawings. Install on interior side of compressor room door or on interior side of door panel.
- D. Operation and Maintenance Data: Collect operation and maintenance manuals furnished by the case and rack OEMs and store them together at the refrigeration rack.
 - 1. Product Data, including rated capacities of selected models, weights (shipping, installed, and operating), furnished specialties and accessories, and installation instructions.

1.4 DELIVERY, STORAGE AND HANDLING

- A. Transport, handle and store products in accordance with the requirements of Section 01600.
- B. Receive Owner furnished products in accordance with the requirements of Appendix A (Section 15600).
- C. Owner Furnished Equipment which is damaged, defective or unsuitable for intended service shall be received by the Contractor and damage noted on the Bill of Lading and signed by the Contractor and Carrier agent. Immediately report Owner Furnished Equipment damage to Walmart Mechanical Construction Manager and include photos of damage and signed Bill of Lading.
- D. Contractor shall furnish a suitable means of securing and protecting all tools, materials, and equipment associated with refrigeration installation during construction period.
- E. Store refrigeration pipe and fittings in a clean and dry location. Receive fittings and store in closed containers or cartons, and store copper piping with rubber end plugs in place. Do not install copper tubing left uncapped for more than one day as refrigeration piping.
- F. Deliver brazing materials, flux, solvents, glues, sealants, insulation materials, lubricants, oils, and refrigerants required to complete refrigeration installation and store on job site in manufacturer's original packaging or crating with labeling intact and fully legible.
- G. Ship insulation materials and accessories such as adhesive and coatings to job site in marked, unopened containers as received from manufacturer. Store materials at job site in a proper manner, which does not damage, deface, or otherwise reduce their serviceability. Store highly flammable solvents, adhesives, and coatings in compliance with OSHA requirements. Store materials, which are susceptible to weather damage in a weatherproof environment and store materials with manufacturer's identification attached.
- H. MSDSs for materials, compounds, and chemicals shall be maintained by the Contractor.

1.5 SEQUENCING, SCHEDULING, AND COORDINATION

A. Sequence, schedule, and coordinate refrigeration installation and start-up activities with Walmart Mechanical Construction Manager to allow the overall project to be constructed in an orderly manner.

- B. Provide personnel as necessary to match schedule needs.
- C. Send a representative to project meetings as required by the General Contractor.
- D. Purchase materials and arrange deliveries in a timely manner to avoid delay of the project. This may include taking early deliveries and off-site storage of items which might be in short supply.
- E. Provide on-site storage container as required. Coordinate with General Contractor for location and availability of on-site storage space. Walk-in cooler and freezer boxes are not to be used for storage.
- F. Notify, coordinate, and correspond with legal authorities having jurisdiction for required inspections of the refrigeration system and piping during the installation process.
- G. Coordinate with Energy Management System Contractor for completion of check-out activities.
- H. Coordinate and confirm system start-up dates with Walmart Mechanical Construction Manager.

1.6 CONTRACTOR RESPONSIBILITIES

- A. Obtain required permits and licenses for installation of refrigeration systems, piping, and equipment prior to start of project.
- B. Assign a competent Project Foreman with a minimum of five years' experience installing supermarket refrigeration systems. Forman shall supervise daily activities associated with installation work including coordinating the activities of each trade as it relates to the refrigeration system installation in order to complete the work on the expected dates; serve as field contact representative and review installation documents for discrepancies. Foreman shall not be changed during the project without permission from the Walmart Mechanical Construction Manager, but may be changed by the Walmart Mechanical Construction Manager with just cause (competency, failure to communicate, or failure to execute direction from the Walmart Mechanical Construction Manager.)
- C. Project Foreman shall attend an OEM system installation training class.
- D. Use Owner's Contract Administration system for contracts, pay applications, potential change orders, change orders, contract documents, and requests for information.
- E. Installation of refrigeration systems involves multiple trades, skill sets, and activities including the following:
 - 1. Receiving, unloading, and setting grocery cases in their proper locations straight and level. This may include both refrigerated and non-refrigerated cases along with case wedges and cap displays supplied by case manufacturers. Align glass doors plumb and level to prevent saw-toothing of doors.
 - 2. Securing, bolting, buckling, sealing, and trimming out cases free of blemishes.
 - 3. Installing case condensate drains independently routed, concealed under cases, properly sloped, supported and trapped, in direction of flow to their designated hub drains or floor sinks.
 - 4. Setting air-cooled or evaporative condensers in their proper locations, level and anchoring them to building structure per structural detail.
 - 5. Provide crane service to hoist refrigeration equipment directly from truck to mounting position.
 - 6. Provide structural support for refrigeration equipment.
 - 7. Provide opening through the roof as applicable.
 - 8. Provide sheet metal refrigeration piping and conduit enclosure as shown on the drawings.
 - 9. Provide opening through outside building wall and provide weather hood as applicable.
 - 10. Setting condensing units in their proper locations level and anchoring them to building structure per structural detail.
 - 11. Setting condensing units and rooftop refrigeration racks in their proper locations, level and anchoring them to building structure per structural detail.
 - 12. Hanging evaporator coils level and tight to ceiling. Route condensate drains tight to walls properly trapped and slope in direction of flow to a hub drain or floor sink.
 - 13. Installing case and walk-in cooler and freezer valves.

- 14. Installing interconnecting refrigeration piping between cases, condensers, evaporator coils, and racks; clean and free from leaks with proper slopes, traps, and sizes.
- 15. Installing refrigeration piping supports as specified.
- 16. Installing refrigeration piping insulation as specified.
- 17. Sealing and restoring vapor barriers for penetrations into walk-in boxes and cases. (Including electrical, alarm, communication, and sprinklers).
- 18. Correctly labeling and tagging refrigeration system equipment and piping as specified.
- 19. Removing and properly disposing of shipping materials, crating, skids, and other construction debris associated with refrigeration system installation.
- 20. Submitting required regulatory forms in a timely manner, carefully and completely filled out. Verisae forms to be submitted at the end of commissioning week.
- 21. Providing all equipment required for the unloading and installation of this scope of work.
- 22. Systematically and thoroughly verifying refrigeration system control functions, sensor calibrations, and review construction activities for quality and completeness. Prepare refrigeration equipment for operation as part of Handover Document completion.
- 23. Thoroughly and systematically pressure testing refrigeration systems. Evacuate and install oil and refrigerant charges. Maintain compliance with regulations governing handling of refrigerants.
- 24. Verify performance of refrigeration systems as part of Handover Documents.

1.7 REQUEST FOR INFORMATION SUBMITTAL

- A. All Request for Information (RFIs) regarding Refrigeration shall follow the attached copy of the Request for Information Process Flow Chart.
- B. Refer to Specification Section 01255 for RFI Information Submittal Process.

1.8 WARRANTY

- A. Provide warranty and service on equipment and materials installed regardless of whether equipment or materials were furnished by Contractor.
- B. Provide supplemental warranty service for all new rack systems. This service will include failures during installation and for 90 days beyond store Re-Grand Opening date. The supplemental warranty shall include labor, parts, primary refrigerant and secondary coolant for repairs to installed refrigeration equipment and piping.
 - 1. Response time to emergency calls shall be within two hours.
- C. For all new rack systems, perform inspection of installation 90 days after store Re-Grand Opening date or when all punchlist items are corrected (whichever is longer). Make necessary corrections and adjustments. Complete refrigeration punch list. Send completed punch list to Walmart Stores, Inc., 2001 S.E. 10th St., Bentonville, AR 72716-0550, Attention: Mechanical Services Department, for verification of completion. Notify Walmart Mechanical Services Construction Manager (MSCM) prior to inspection.
- D. For all new rack systems, at 90 day inspection, include necessary lubrication, leak tests of all joints, flare nuts, and tightening of strapping as necessary. Perform leak test on small leak setting of refrigerant leak detector. Provide and change liquid line filter cores, oil system filter using Sporlan OF style filter, and replace suction filters. Place suction, liquid, and oil filters in a sealable plastic bag to prevent setting off any leak detection system. Perform oil acid test using either Virgina's TKO acid test kit (mineral or Alkylbenzene oil) or Virgina's ETK acid test kit (POE oil). For new rack house scenarios, oil test will be certified to meet OEM standards by Walmart Refrigeration Engineer of Record. If oil test results require an additional oil change, it will be performed by Walmart. Leave oil filters in motor room for inspection by Walmart Mechanical Services Construction Manager. Contractor to properly dispose of oil and components replaced.
- E. Owner's equipment manufacturer (OEM) supplier will furnish replacement parts for failures of OEM parts during installation period and for one year beyond store RE-Grand Opening date. Contractor shall obtain replacement parts from equipment manufacturer. Owner will not pay additional costs associated with repair or replacement of materials and parts during the warranty period.

- F. In the event the Contractor fails to respond to emergency calls or fails to perform required maintenance or repairs during warranty period, the Owner will have the right to have the repair or maintenance performed by another contractor. In this case, the Contractor agrees to pay the Owner the invoiced amount of the services performed plus 15 percent.
- G. If the service contractor discontinues or drops their service level because the Contractor has failed to make payment to subcontractor on completed warranty work, Walmart will remove that Contractor from New Stores Bid List until such time when all disputes or claims are settled.
- H. At the end of warranty period, certify in a letter to the Owner that equipment and materials installed or connected are functioning properly. Include certification that systems are free of leaks and are maintaining satisfactory temperatures at normal control adjustments.

PART 2 - PRODUCTS

2.1 OWNER FURNISHED PRODUCTS

- A. Owner will furnish refrigeration equipment as scheduled and shown on Drawings and as specified in Appendix A (Section 15600) for installation by the Contractor which includes, but not limited to, the following:
 - 1. Condensers.
 - 2. Condensing Units.
 - 3. Evaporators.
 - 4. Compressor Rack Systems.
 - 5. Refrigerated cases.
 - 6. Ice flakers.
 - 7. Produce misting system.

2.2 OWNER FURNISHED AND INSTALLED PRODUCTS

- A. Owner will furnish and install refrigeration equipment as scheduled and shown on Drawings which includes, but not limited to,the following:
 - 1. Walk-in Freezers and Coolers.

2.3 MATERIALS (CONTRACTOR FURNISHED AND INSTALLED)

- A. Refrigerant Systems: Furnish and Install piping for refrigeration systems as specified in Schedule I below and as indicated on Drawings.
 - 1. Refrigerant Copper Tubing and Fittings: ASTM B 280, type ACR, hard drawn tubing. Tubing shall be factory cleaned, ready for installation, and have ends capped to protect cleanliness of pipe interior prior to shipping. Provide wrought copper pressure fittings, ANSI B16.22.
 - Provide copper tubing from one of the following manufacturers:
 - 1) Cerro Flow Products
 - 2) Mueller Industries
 - Provide copper fittings from one of the following manufacturers:
 - 1) Mueller Industries
 - 2) Nibco
 - 3) <u>NDL Industries, Inc.</u>
 - c. ABS Piping and Fittings: BS 5391 and BS 5392, manufactured for class E pressure bearing service.
- B. Condensate Systems: Provide piping for condensate systems as specified in Schedule I below and as indicated on Drawings.
 - 1. Copper Tubing and Fittings: Type M, hard drawn tubing.PVC Piping and Fittings: ASTM D2665, schedule 40 drain, waste, and vent.
- C. Piping Insulation:

a.

b.

1. Elastomeric Flexible Closed Cell Insulation: Maximum k factor at 75°F of 0.28 Btu-in/hr-ft²-°F, maximum flame spread and smoke development of 25 and 50, respectively per ASTM E84.

- 2. Provide one of the following, thicknesses as specified in Schedule I below:
 - a. AP Armaflex by Armacell.
 - b. Aerocell by Aeroflex USA, Inc.
 - c. Insul-Tube by K-Flex USA.
- 3. Cladded Insulation:
 - a. Provide cladded insulation for insulated exterior refrigerant piping.
 - b. Provide insulation from the approved list of manufacturers with factory or field installed PVC jacketing or cladding. PVC jacketing or cladding shall match the insulation color requirements.
 - c. PVC jacketing and fitting covers shall be by one of the following:
 - 1) Proto PVC Fitting Cover System by Knauf Insulation
 - 2) Zeston PVC Fitting Cover System by Johns Manville,
- 4. Insulated tape, half lapped, triple reversed layered may be used to insulate valves, valve stations and factory installed piping components within cases.
- 5. Insulation color: black.
 - a. When re-insulating lines provide split seam insulation meeting ASTM C534, pre-glued with pulltape type seam on longitudinal joint and flap that seals the longitudinal seam. The only acceptable product numbers are: Aerocel-SSPT by Aeroflex USA, Inc (black).

Schedule I					
Piping Service	Piping Size	Piping Material	Insulation Thickness		
R404A/R407A/R22 - Suction	1-3/8 inches and smaller	Type L Hard Drawn Copper, Sealed ACR Tubing	1 inch		
R404A/R407A/R22 - Suction	1-5/8 inches and larger	Type L Hard Drawn Copper, Sealed ACR Tubing	1-1/2 inch		
R404A/R407A/R22 - Liquid	All	Type L Hard Drawn Copper, Sealed ACR Tubing	1/2 inch		
R744 – Carbon Dioxide	1-3/8 inches and smaller	Type L Hard Drawn Copper, Sealed ACR Tubing	1-1/2 inch		
R744 – Carbon Dioxide	1-5/8 inches and larger	Type K Hard Drawn Copper, Sealed ACR Tubing	1-1/2 inch		
Propylene Glycol / Water	1-3/8 inches and smaller	Type L Hard Drawn Copper or Pressure Rated ABS	1 inch		
Propylene Glycol / Water	1-5/8 inches and larger	Type L Hard Drawn Copper or Pressure Rated ABS	1-1/2 inch		
Evaporator Condensate - Inside Refrigerated Walk-in Boxes Operating at 32°F or Below	All	Type L Hard Drawn Copper	1 inch		
Evaporator Condensate - Outside Refrigerated Walk-in Boxes and Inside Boxes Operating Above 32°F	All	Schedule 40 PVC, Solid Core, DWV	N/A		

D. Refrigerant Valves:

- 1. Isolation valves shall be full port ball type valves, with a minimum working pressure of 700 PSIG, a working temperature range of -40°F to 300°F, and specifically designed for use with the refrigerant that is contained within the system. The valve body shall be forged brass and hermetically sealed. Bolted body valves are not permitted.
- 2. Provide valves as manufactured by one of the following:
 - a. Henry Technologies.
 - b. Mueller Industries.
 - c. NDL Industries, Inc.
- E. Pipe Freeze Protection:

- 1. Heating cable shall be self regulating, 120 volt, 5 watts per linear foot.
- 2. Provide one of the following:
 - a. Raychem XL-Trace by Tyco Thermal Controls, LLC.
 - b. CO Series by Delta-Therm Corporation.
- F. Refrigerants and Oils:
 - 1. Refrigerant: As specified on Refrigeration Equipment Schedules and certified to meet AHRI 700 standard for chemical purity. Deliver refrigerant in original containers.
 - 2. Refrigerant Oil: Approved for use by compressor manufacturer, with refrigerant and compressors for the application. Do not put oil in systems from containers that have been left uncapped for an extended period of time.

PART 3 - EXECUTION

- 3.1 INSTALLATION
 - A. General Installation Requirements:
 - 1. Equipment:
 - a. Install refrigeration equipment in accordance with manufacturer's instructions.
 - b. Attach rooftop refrigeration equipment to structural support frame or roof curb as shown on Drawings.
 - c. Ppipe routing, case, condenser, and compressor rack locations shall not deviate from Drawings without approval from Walmart Mechanical Construction Manager.
 - 2. All Piping:
 - a. Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate the general location and arrangement of piping systems. Locations and arrangements of piping take into consideration pipe sizing and friction loss, expansion, pump sizing, and other design considerations. So far as practical, install piping as indicated.
 - b. Install piping in a neat and workmanlike manner with pipe sizes as indicated on the drawings.
 - c. Inspect materials to verify they are free of defects, grease, and foreign particles; comply with the temperature and pressure rating of the system; and are compatible with the refrigerant in the system.
 - d. Suspend refrigeration piping as shown on Drawings, with supports spaced in accordance with the requirements of Section 15050.
 - e. Ream cut ends to full interior diameter and remove burrs created during cutting process.
 - f. Remove oxides and surface soil from pipe ends and fitting cups with abrasive cloth, abrasive pads, or properly sized fitting brush.
 - g. Install piping with sufficient flexibility to allow for expansion and contraction due to temperature fluctuations inherent in operation of these types of refrigeration systems. Install piping to prevent vibration and undue strain on pipe and fittings.
 - h. Maintain refrigerant piping clean and dry. Keep piping sealed when not working directly at a specific location or joint. Do not leave open refrigerant piping ends unattended during installation process. Fitted joints exposed to the exterior of the building shall be brazed the same day they are fitted. Visibly inspect pipe and fitting prior to assembly. Swab as necessary with cleaning solvent soaked cloth to remove dirt, filings, or visible moisture.
 - i. Prevent piping contact at pipe crossings by use of offset and/or insulation. Refrigerant piping shall not contact-electrical conduit or other dissimilar grounded metals.
 - j. Provide branch supply and return line ball valves for isolation purposes as indicated on refrigeration piping plans. Install valves in a fully accessible location. Insulate isolation valves in accordance with refrigeration line insulation requirements.
 - k. Install exposed piping at right angles or parallel to building walls. Diagonal runs are not permitted unless expressly indicated.
 - 1. Conceal all pipe installations in pipe chases, utility spaces, and above ceilings, unless indicated to be exposed to view.
 - m. Install horizontal piping as high as possible allowing for specified slope and coordination with other components. Install vertical piping tight to columns or walls. Provide space to permit insulation applications where required, with one inch clearance outside the insulation. Allow sufficient space above removable ceiling panels to allow for panel removal.

- n. Locate groups of pipes parallel to each other, spaced to permit applying insulation and servicing of valves.
- o. Secure vertical refrigerant piping installed outside building walls to Unistrut fastening system with #022 Cush-a-Clamps. Fasten clamps directly to copper pipe, not to outside of insulation. Butt insulation against clamp and insulate uncovered.
- p. In general, clamps are not required on horizontal piping. However, horizontal piping that is vertically supported without support directly under the piping shall be clamped.
- q. Make copper piping soft solder joints with specified solder and flux. Clean joints before soldering.
- r. Make brazed joints with use of brazing alloy containing minimum of 15% silver. Clean joints before brazing and have dry nitrogen at 1/2 psi pressure flowing through tubing during brazing.
- s. Protect affected valves and control devices during brazing process by disassembling and removing heat sensitive parts or use of heat shields.
- t. Install replacement parts (i.e. expansion valves, heat exchangers, sight glasses) using specified solder, excluding parts in hot gas lines. Use heat dams in all instances.
- u. Walmart Mechanical Construction Manager shall visually inspect refrigerant piping and insulation prior to being covered.
- v. Piping deemed by the Walmart Mechanical Construction Manager to be installed incorrectly shall be corrected at Contractor's expense.
- 3. Insulation:
 - a. Install refrigeration piping insulation in accordance with ASTM C 1710, manufacturer's recommendations and per schedule I including glued and taped joints.
 - b. Ensure that temperature and other environmental conditions are favorable for installation of insulation materials.
 - c. Coordinate with other trades so that work is performed with minimum interference and conflict. Carefully note heat tracing and pressure testing procedures prior to installation of insulation materials. Do not apply insulation covering pipe or fitting joints until after pressure testing affecting those joints has been completed and approved by Walmart Mechanical Construction Manager and Authority Having Jurisdiction.
 - d. Do not apply insulation until surfaces are clean, dry, and free of dirt, grease, moisture or other impurities such as corrosive cleaners and dust. Seal refrigerant pipe openings while installing insulation to prevent foreign material from entering tubing.
 - e. Insulation work shall be performed by trained installers regularly engaged in insulation trade.
 - f. Cleanly and squarely cut insulation joints. Do not tear insulation.
 - g. Install piping insulation continuous through sleeves and penetrations (walls, partitions, roofs, ceilings, and floors).
 - h. Seal seams, butts, and ends to retard moisture vapor from entering system. Glue joints with approved products. Do not stretch insulation as it is being installed and glued.
 - i. Vapor stop exposed ends and every 12 feet by applying approved contact adhesive to outside surface of piping and inside surface of insulation and secure to piping.
 - j. Insulate fittings, flanges, and valves with same insulation thickness as adjacent piping.
 - k. Insulate valves to a point just below seal cap or packing gland. Seal insulation to valve body with contact adhesive.
 - 1. Slip insulation over pipe before making joints. Split type insulation is acceptable on fittings only. Provide factory pre-manufactured insulation fittings. Where pre-manufactured fittings are unavailable, miter cut fittings shall be used with approval of Owner's Mechanical Construction Manager. Install insulation in conformance with manufacturer's recommendations, including glued and taped joints. If receiver is mounted outside, provide UV protection for pipe insulation on the liquid line from the receiver to the refrigeration rack by application of a covering or coating specifically for the purpose of UV protection and as recommended by the manufacturer.
 - m. Cover exterior refrigerant pipe insulation (including heat reclaim lines) and interior prep room lines with .020 inch thickness UV inhibited PV jacketing and fitting covers. Seal jacketing against vapor and weather.
 - n. Install insulation in such a manner to ensure a properly functioning system. Reinstall an installation that is deemed unacceptable by the Walmart Mechanical Construction Manager.
- 4. Penetrations:
 - a. Seal penetrations through exterior building walls and walk-in coolers and freezers with urethane foam and silicone caulk as specified in Section 07900 and as detailed on Refrigeration Drawings.

- b. Fire Barrier Penetrations: where pipes pass through fire rated walls, partitions, ceilings, and floors, maintain the fire rated integrity. Provide fire stopping in compliance with the requirements of Section 07840.
- 5. Electrical:
 - a. Make final electrical connections, including slave wiring, to refrigerated cases, evaporators, field installed refrigeration control valves, defrost heaters, cooler and freezer box door lights and antisweat heaters, and compressor houses. Make connections per wiring diagrams and instructions from equipment supplier. Comply with the requirements of Section 16100 and applicable electrical codes.
- 6. Control Tubing:
 - a. Install tubing such that there is sufficient slack. Avoid stretching and sharp bends. Properly support tubing away from contact with sharp or abrasive objects.
 - b. Always connect control tubing to refrigeration system or components through a service valve.
 - c. Remove breakaway Schrader valve depressor.
 - d. Do not over torque flare nuts.
- 7. DX System Installation Requirements:
 - a. Install electronic suction pressure regulator valves, thermostatic expansion valves, liquid solenoids, thermostats, and heat exchangers. Provide sufficient pipe at evaporator outlet to install thermostatic expansion valve sensing bulb, ensuring 100% contact with pipe.
 - b. P-Traps shall be one piece, short radius type at bottom of risers. Size P traps to match horizontal pipe or coil outlet pipe. Do not reduce trap to riser size. Take vertical risers as high as possible (just below structure). On risers above 16 feet, provide double oil traps spaced as shown on Drawings.
 - c. Pitch horizontal suction lines minimum of one inch per 20 feet of run in direction of refrigerant flow. Ensure no oil traps are formed in piping layout.
 - d. Liquid supply line tees shall be bullheaded inside cases. Suction lines shall not be bullheaded.
 - e. Install 1/4 inch packed angle king valve on top of inverted trap on inlet side of field installed condensers. Install valve at highest point in the discharge line. Provide packed angle valves with brass or steel caps.
 - f. Suction lines and return lines that are teed into a common return line shall be teed into the top. Liquid lines shall come off of the bottom.
 - g. Provide Schrader valve access on each suction line leaving evaporators.
 - h. Verify Schrader valves have cores securely installed and caps are installed.
- B. Condensate Piping System Installation Requirements:
 - 1. Provide condensate lines from evaporators to outside of walk-in freezers and coolers, and adapt to individual PVC trap.
 - 2. Clean markings off of PVC with solvent.
 - 3. Install self-regulating heating cable and insulation on condensate drains inside walk-in boxes that are to operate at or below 32°F.
 - 4. Install unions on condensate drains in walk-ins close to drain pan.
 - 5. Allow clearance for evaporator drain pans to hinge open. Install common condensate header outside the walk-in and terminate condensate lines into header.
 - 6. Paint non-insulated copper drain lines to match walk-in box.
 - 7. Maintain slope of one inch per ten feet of horizontal run for condensate lines.
- C. Hangers and Supports:
 - 1. Install hangers, supports and anchor devices as specified in Section 15050.
 - 2. Install hangers and supports to allow controlled movement of piping systems, permit freedom of movement between pipe anchors, and accommodate normal expansion and contraction due to changes in temperature.
 - 3. Install hangers and supports so that piping live and dead loading or stresses from movement are not transmitted to connected equipment.
 - 4. Install hangers for insulated pipe sized to encompass insulation including support shields.
 - 5. Where pipes of various sizes are supported together by trapeze hangers, space hangers for the smallest pipe size or install intermediate supports for smaller diameter pipes.
 - 6. Adjust hangers to distribute loads equally on attachments and achieve the indicated slope of piping.
 - 7. Remove sharp edges and burrs from refrigeration system hangers and supports.
 - 8. Remove excessive rod materials from hangers that protrude 2 inches or more from the hangers after adjusting and pitch have been established.

3.2 IDENTIFICATION

- A. Case, Walk-In, and Evaporator Identification:
 - 1. Provide engraved plastic identification tags 2 inch by 3 inch in size, attached with screws, pop rivets or adhesive to case, Walk-In, and Walk-In evaporator.
 - 2. Identify circuits with corresponding number and circuit from REM plans.
 - 3. Identify cases with an approximate location of field installed control valves.
- B. Refrigeration Equipment Identification:
 - 1. Provide engraved plastic identification tags 2 inch by 3 inch in size, attached with screws or pop rivets.
 - 2. Identify refrigeration equipment, including compressor houses, racks, condensers, sensor or thermostat locations, and hot water tanks.
 - 3. Valve Nameplates: Provide factory custom-stamped metal identification tags for field installed refrigeration system control valves and flow sensors as scheduled on the drawings.
 - 4. Tags shall be brass material and shall be securely attached to valve or sensor body.
 - 5. Provide tags by Emedco.com, (866) 222-4743 or equivalent.
- C. Nameplates and labels shall be installed prior to refrigeration system start-up.

3.3 CASE SETTING

- A. Set cases level and in line with transit. Shim at each vertical support or at maximum four foot intervals with galvanized plates, as floor conditions require. Where manufacturer's installation instructions differ from Owner's specifications, consult with Walmart Mechanical Construction Manager.
- B. Install cases per manufacturer's installation instructions. In addition, aply butyl caulking compound all around case joints. Reseal joints if seal is broken.
- C. Install a bead of butyl sealant and cover with clear tape on the top and back exterior joints for glass door cases.
- D. Install a finish bead of silicone on interior case joints (bottom, back and interior top of case). Sealant shall match case interior color.
- E. Do not cut bottom case rails.
- F. Hang case shelving and place pans in refrigerated cases, including door shelving in dairy cooler.

3.4 WALK-IN COOLER/FREEZER EVAPORATOR COILS

- A. Examine areas to receive equipment, review proposed locations of equipment and piping, and verify that they are free of interferences. Comply with requirements for installation tolerances and other conditions affecting unit performance.
- B. Locations of equipment on Drawings are approximate. Field verify exact locations before roughing in piping and electrical work.
- C. Accurately layout, mark, and drill necessary holes in walk-in box panels. Cut holes only with drill bits and hole saws. Cut holes only as large as required to accommodate pipes, hanger rods, and conduits, refer to drawing detail for piping penetrations.
- D. Hang or mount evaporator coils plumb and level in accordance with manufacturer's instructions and Refrigeration Drawings.
- E. Maintain manufacturer's recommended clearances so as to not restrict air flow.
- F. Support piping separately so that piping is not supported off of evaporator coil units.

- G. Install electrical devices furnished by manufacturer.
- H. Install interconnecting refrigeration piping between evaporator coils and refrigeration piping.
- I. Install horizontal suction pipe extension for installation of TXV sensing bulb. Bulb shall be in direct contact with refrigeration piping and not installed on any braze joint.
- J. Install walk-in cooler/freezer refrigerant sampling intake devices and necessary interconnecting tubing back to refrigerant detection units.
- K. Install condensate lines for walk-in coolers/freezers.
- L. Install heat trace and insulation for condensate drain lines in walk-in coolers/freezers operating below 32 F.
- M. Fit condensate lines in walk-in coolers/freezers with a union to facilitate cleaning of condensate line and removal of evaporator coil drain pan.

3.5 TESTING, EVACUATING, CHARGING, AND FILLING DX REFRIGERANT SYSTEM

- A. Notify Walmart Mechanical Construction Manager 72 hours in advance of pressure/vacuum and evacuation tests.
- B. Testing
 - 1. When refrigeration connections have been completed, test refrigerant piping system for leaks with dry nitrogen at a minimum of 150 PSIG, but not to exceed 200 PSIG, with all valves in the system open except compressor suction and discharge valves relief valves, and transducers which must be kept closed during pressure testing and evacuation procedures.
 - 2. Physically test all joints with a soap solution.
 - 3. System shall hold maximum pressure for 24 hours.
 - 4. If leaks are found, isolate leaks, discharge gas, repair leaks, and then repeat test.
 - 5. Do not release pressure until making final connections.
- C. Evacuating
 - 1. Evacuate system with a 2 stage vacuum pump specifically manufactured for vacuum duty and having capacity of at least 6 CFM and the capability of pulling vacuum of 50 microns or less within a 24 hour period. Do not evacuate system by use of the refrigeration compressor. Connect pump to both low and high side evacuation valves with copper tube. Compressor service valves shall remain open. Attach high vacuum gage, capable of registering pressure in microns, to system for pressure readings. Do not operate hermetic or semi-hermetic motor compressors during evacuation because of reduced electric strength of atmosphere within motor chamber. To check system pressure, provide hand valve between pressure gage and vacuum pump which can be closed to isolate system and check pressure.
 - 2. Isolate transducers from vacuum testing.
 - 3. Evacuate each system to an absolute pressure not exceeding 1,500 microns.
 - 4. Break vacuum to 2 PSIG with dry nitrogen.
 - 5. Repeat evacuation process two more times.
 - 6. Install drier of required size in liquid line.
 - 7. Leave vacuum running for not less than two hours without interruption, valve off, and remove vacuum pump.
 - 8. Evacuate system to 500 microns and hold for 24 hours.
 - 9. Verify vacuum procedure and test with Walmart Mechanical Construction Manager.
 - 10. Break final vacuum to 2 psig with specified refrigerant.
- D. Charging and Filling
 - 1. Provide primary refrigerant as indicated on refrigeration Drawings and as required for proper operation of systems. Check the refrigeration Drawings and the equipment manufacturer's labeling prior to charging of refrigeration system.
 - 2. Add refrigerant to system through a liquid line filter/dryer in charging line.
 - 3. Charge refrigerant directly from original containers.

- 4. Charge system according to OEM procedures.
- 5. Record amount of refrigerant used on Owner provided Verisae form. Email to mcequip@Walmart.com and Walmart Mechanical Construction Manager.
- 6. Write refrigerant charge per rack in black indelible marker on each system compressor breaker panel.
- 7. Fill compressors with oil to manufacturer's recommended levels and fill oil reservoirs to 1/2 full. Top off the reservoirs with oil after the system has run for a minimum of 24 hours.
- 8. Refrigerant charge shown on Refrigeration Drawings is a calculated estimate only. Fully charge refrigeration system at start-up.

3.6 PRE-START-UP

- A. Document the following Pre-Start-Up information, at a minimum, on Handover Documents
 - 1. Check electrical connections at rack. Turn main breaker OFF and verify that no power is present at all three legs with a meter. Verify tightness of electrical connections.
 - 2. Check main power voltage across each supply leg at the compressor rack. Voltage shall be within 10 percent of required.
 - 3. Check control voltage.
 - 4. Energize system for 24 hours in advance of starting any compressor.
 - 5. Verify cleanliness of evaporator coils
 - 6. Verify proper expansion valve installation.
 - 7. Verify that evaporator and condenser fans are clear of debris.
 - 8. Verify evaporator fan operation.
 - 9. Verify that case, walk-in cooler/freezer doors close properly and are closed.
 - 10. Verify operation of case lights and switches.
 - 11. Verify that door seals are not damaged.
 - 12. Verify high and low pressure control settings.
 - 13. Verify that field wiring connections have been completed.
 - 14. Verify condenser pressure fan cycling control operation.
 - 15. Verify temperature set-points.
 - 16. Verify alarm set-points.
 - 17. Verify defrost schedule.
 - 18. Verify that compressor discharge service valve is fully open.

3.7 SYSTEM START-UP

- A. Refer to equipment manufacturers start-up documentation for additional requirements.
- B. Schedule start-up so that refrigeration systems are operational and running prior to manufacturer representative visit to perform system commissioning with the Contractor.
- C. Include qualified service technicians, necessary tools, and other supplies required by manufacturer's field service representative to perform commissioning activities identified in Contract Documents.
- D. Conduct system start-up as follows:
 - 1. Adjust valves, expansion valves, liquid hold-back valves, balance valves, compressor high and low pressure switches, receiver pressurization, and subcooler outlet pressure regulator.
 - 2. Complete refrigerant and oil charge.
 - 3. Adjust oil float levels and replace liquid, suction, and oil line filter/dryers.
 - 4. Verify pressure and temperature gauges are accurate.
- E. After compressor is started, continue charging until system has sufficient refrigerant for proper operation. Do not charge receiver level past 40%. Do not leave compressor operating unattended and unmatched until system is properly charged with refrigerant and oil. Charge receivers to 30 percent with unit in heat reclaim in 100 percent condenser and condenser fan controls set properly. Maintain these levels throughout maintenance service period. If at end of maintenance period, receiver level has dropped, completely re-check refrigeration rack and case system for leaks. Repair leaks and bring system back to original charge level.

- F. Do not add oil while system is short of refrigerant unless oil level is inadequate for system operation.
- G. Set expansion valve superheat on systems per manufacturer's recommendations. Balance multi-plex systems to within 2°F of target and with not more than 2°F variation in discharge air temperature between cases. Verify superheat settings after fixtures have been loaded with product.
- H. Prior to opening any rack systems to add or replace cases, evaporators, etc, install new suction filter in the suction line canister. Then 24 to 48 hours after the work is completed and all final adjustments have been made, provide and change liquid line filter cores, oil system filter using Sporlan OF style filter, and suction filters. Filters are to be rated for wax removal. Contractor to properly dispose of oil and components replaced.
- I. Test and adjust controls to ensure a refrigeration system operating to Owner's design specifications.
- J. Run refrigeration system for a minimum of 100 hours prior to turnover to Owner for merchandising or stocking. 100 hour run time begins when refrigeration system is running and connected loads are at correct operating temperatures. 100 hour period is to be used to adjust expansion valves, calibrate sensors, etc.
- K. Verify refrigeration alarm system is functioning correctly 24 hours prior to food delivery.
- L. Complete system balance by the end of the fifth day of start-up.
- M. Complete Refrigeration Installation Handover Document / Sign Off Sheet and submit as specified in Part 1.
- N. Final payment will not be made until Refrigeration Installation Handover Document / Sign Off Sheet and Verisae documentation is received and job notebook is completed and placed in the mechanical refrigeration house.

3.8 CONTRACT COMPLETION, STORE POSSESSION AND RE-GRAND OPENING DAY

- A. Coordinate and execute the Handover Documents as soon as final system adjustments are completed.
- B. Finish work and furnish Owner's Mechanical Construction Manager with a complete and operating refrigeration system at Contract Completion.
- C. Owner may take possession of completed or partially completed portions of work although time allotted for completion of work may not have expired. Taking possession of work shall not be deemed acceptance of any work that has not been completed in accordance with Contract Documents.
- D. Temperature and valves shall be adjusted and control strategies modified as necessary as cases are loaded with product and conditions within store environment change.
- E. Have a mechanic on job site from 7:00 AM to 6:00 PM on the day before Re-Grand Opening and the day of Re-Grand Opening. Mechanic shall check in with both the Store Manager and the Field Project Manager when arriving and prior to leaving.

3.9 FIELD QUALITY CONTROL

- A. Maintain a clean and orderly work area. On a weekly basis remove from jobsite scrap, waste, and debris resulting from refrigeration field work.
- B. Installation materials shall be new and without defect. If requested, Contractor shall submit evidence as to quality of systems built, including but not limited to, material test reports, packing slips, material data sheets, employee qualification and training documentation records, brazed joints, insulation mock ups, leak testing and electrical function testing records.
- C. Prior to concealing joints with insulation or piping in walls, floors, or ceilings, clean and test piping in accordance with these specifications. Piping shall be leak-free.

- D. Contractor shall assure quality of brazing done by their organization and shall employ skilled craftsmen following qualified brazing procedures. If directed by the Walmart Mechanical Construction Manager, cut out five randomly selected joints to verify use of dry nitrogen during brazing operations. Inspect joints for oxidation in the presence of the Mechanical Construction Manager. For each joint which shows evidence of oxidation, cut out an additional joint. If four fittings are found oxidized, rework all joints including those removed for inspection.
- E. On completion of refrigerated work, remove tools, equipment, excess materials, scrap, waste, and other debris resulting from work, and clean walk-in coolers/freezers, cases, roof areas adjacent to condensers, and refrigeration compressor house.

3.10 MAINTENANCE

- A. Provide a 90 day maintenance service period from the date of Re-Grand Opening to include maintenance and assurance of proper operation of the entire refrigeration system. The service period shall include maintenance for primary refrigerant and routine maintenance and emergency services. Upon start-up, submit the names of local service companies authorized by the OEM for maintenance service to MCM.
- B. Response time to emergency service calls shall be within two hours. In the event the Contractor fails to respond to emergency calls or fails to perform required maintenance or repairs during the maintenance period, the Owner will have the right to have the repair or maintenance performed by another contractor. In this case, the Contractor agrees to pay the Owner the invoiced amount of the services performed plus 15 percent.
- C. If the service subcontractor discontinues or drops their service level because the Contractor has failed to make payment to the subcontractor on completed maintenance work, Owner may remove the Contractor from bidder eligibility for future new store work until such time that disputes or claims are settled.
- D. Perform inspection of installation at end of maintenance service period.
 - 1. Make necessary corrections and adjustments. Notify Walmart Mechanical Construction Manager (MCM) prior to inspection.
 - 2. Provide lubrication, leak tests of all joints, flare nuts, and tightening of strapping. Perform leak test on all fixtures and rack service points, fittings and valves.
 - 3. Change replaceable suction, liquid, and oil filters. Place suction, liquid, and oil filters in a sealable plastic bag to prevent setting off any leak detection system. Leave oil filters and dryers in motor room for inspection by Walmart Mechanical Construction Manager.
 - 4. Assure all deviations have been resolved.
- E. At the end of maintenance services period, certify in a letter to the Owner that equipment and materials installed or connected are functioning properly. Include certification that systems are free of leaks and are maintaining satisfactory temperatures at normal control adjustments.

END OF SECTION

Store No	Location:	Store Type:	
	City, State	S	C, SAMS, NM
Grand Opening Date:			
Project Type:	New SC Store/ Sam's Clu	b, Relocation, Remodel, Capital Expenditu	ire (CapEx)
Installing Contractor:	Contractor's name and bra	anch location, if applicable	
Equipment Supplier:	Hill PHOENIX, Kysor W	arren, Zero Zone, Hussmann	
Refrigerant:	R 407A, R410A, etc.		
System Type:	Direct Expansion (DX)		
Heat Reclaim:	Domestic Water, N/A		
Bldg Automation System	n (EMS): Novar, Danfoss, CPC		
Verisae Data Submitted:	Date Submitted or N/A		
Comments:			

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET

All sections of this document must be completed before the installation will be accepted.

APPROVAL

The work carried out during this project is complete and the standard achieved is acceptable.

Name of Walmart Mechanical	Signature	Date
Construction Manager		
Notice to OWNER'S MCM:		
By signing this form, you are confirming the follo	owing:	
The work detailed above is complete and all syste	ems are operating as intended.	
All handover documentation has been completed	and you are satisfied with its contents.	
All issues are either resolved or you are satisfied	with the plan for resolution.	

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET Machine Rooms

Store No I	Location:	Store Type:	
	City, State	SC, SAMS, NM	
Name of technician carryin	ng out checks and completing this form	Date	
Type of machine room	Rack, hybrid house, weatherpac		
Machine room supplier	Hill PHOENIX, Kysor Warren, Zero Zone		
Are weatherpacs bolted to	steel?	yes / no	
Are all penetrations proper	rly sealed?		
Do all power sockets and l	ights operate correctly?		
Do all exhaust fans operate	e correctly?		
Are all weatherpac doors h	nung properly and operating correctly?		
Is there any damage to the	room which needs repair?		
Are all shields and hoods i	nstalled correctly?		
Are Operation and Mainte	nance (O and M) manuals left on site?	yes / no	
Are drawings mounted on	the walls of machine rooms?	yes / no	
Have liquid line filter drye been changed after 24	rs, oil system dryers, and suction line filter drier hours of run time?	s yes / no	
Is leak detection installed?		yes / no	
Has leak detection been te	sted and certified functional?		
Are electrical drawings mo	ounted inside electrical panels?	yes / no	
Are all electrical distributi	on panels labeled correctly?	yes / no	
Are all trunking lids and ju	unction box covers in place?	yes / no	
Have all relevant labels be	en fixed to major items of equipment?		
Is the machine room clean	and free from rubbish?	yes / no	
Capital Expenditure (CAP	EX) and Remodel Projects		
Have all existing, redunda been stripped out or n	nt materials (conduit, pipework, etc.) nade safe?	yes / no	
Comments:			

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET Refrigeration Vacuum Test

Store No	Location	n:		Store Type:		
		City, State			SC, SAMS, I	NM
Owner's Constru	ction Manager					
	e					
Installing Contract	ctor					
Contractor's Add	rass					
Contractor 5 Add	1035	Street				
		City, State, Z	IP			
Contractor's Pho	ne					
Contractor's Ema	il Address					
Name of Person A	Attesting to Vacu	uum				
	Resting to viet				Phone	
Gauge Used for T	Testing					
Manufacturer		Type		Model #	Range in N	Aicrons
Winnundeturer		rype			Runge in i	nerons
	А	В	С	D	Е	F
First						
Second						
Final						
Date of Final						
Pressure at						
Check In						
CHCck-III						
Check-III						
Check-III						
Signature					Date	
Signature Comments:					Date	
Signature Comments:				 	Date	

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET Rack A

Store No.	Location:	Location:			Store Type:		
	City, State			_ ,	SC, SAMS, I	NM	
Name of tech	nnician carrying out chec	ks and completing thi	is form		Date		
Rack Type							
Rack Manufa	Parallel Recip, acturer	Rack in a Box (RIB).	, Modular				
Rack Model	No		Rack Serial No.				
Refrigerant T	Гуре		Record System R	efrigerant Cha	rge		
Does the refr	rigerant type match what	is called for on the le	gend?		yes / 1	no	
Verify the ma	ain power voltage.	L1 > GD L2 > GD L2 > GD	L1 > I L1 > I L1 > I L1 > I	.2 .3			
Verify the co	ontrol voltage.						
Confirm oper	ration of power failure (l	PF) module and record	d settings. Delay _		Voltage		
Are all electr	rical connections tight?	yes / no					
Compressor 1	Manufacturer						
Record mode	el number of each compr	essor. Verify that mo	del numbers match le	gend.			
Compressor Compressor Compressor	1 3 5 ing amps for each compr	essor.	Compressor 2 Compressor 4 Compressor 6				
COMP 1 Loaded Unloaded	L1 L2 L1 L2	L3 L3	COMP 2 Loaded Unloaded	L1 L1	L2 L2	L3 L3	
COMP 3 Loaded Unloaded	L1 L2 L1 L2	L3 L3	COMP 4 Loaded Unloaded	L1 L1	L2 L2	L3 L3	
COMP 5 Loaded Unloaded	L1 L2 L1 L2	L3 L3	COMP 6 Loaded Unloaded	L1 L1	L2 L2	L3	

Allow the oil pressure switch to trip on each compressor to or minutes and check crankcase heater operation. Record amp C1 C2 C3 C4	ensure proper draw of each C5	operation. After oil press crank case heater. C6	ure trips, wait two
Adjust and record compressor's start delay timer setting.	 C5	C6	
Adjust and record compressor's HP cut out switch setting. C1 C2 C3 C4	C5	C6	
Is EMS suction transducer calibrated?			yes / no
Record the EMS rack suction pressure settings.	Cut In	Cut Out	
Check and record the rack suction pressure.	EMS	Gauge	
Check and record the suction temperature.	EMS	Meter	
What is the rack superheat?			
Have all Evaporator Pressure Regulators (EPRs) been set co	orrectly?		yes / no
Note: Individual EPR settings to be recorded on case start-u	ip documents.		
Check and record the ambient temperature.	EMS	Meter	
Is EMS discharge transducer calibrated?			yes / no
Check and record the discharge pressure.	BAS	Gauge	
Check and record the discharge temperature.	BAS	Meter	
Check and record the drop leg temperature.	BAS	Meter	
Does this rack have hot water / heat reclaim?			yes / no
Record heat reclaim control settings. Reclaim t'stat		Electric heater t'stat	
Note: Reclaim thermostat should be set to 140°F. Electric b	back up therm	ostats should be set to 130	°F.
Check and record correct heater element voltage.		-	
Record the rack high pressure BAS lockout setting.		-	
Does this rack have ambient subcooling (surge)?			yes / no
Check and record the BAS surge setpoints.	Cut In	Cut Out	
Check for correct operation. Is system operating OK?			yes / no
Does this rack have subcooling?			yes / no
Record liquid subcooling temp BAS set point.			
Record actual liquid temperature.			

Record outlet pressure regulator (OPR) setting (if applicable).	
Record bypass valve setting (if applicable).	
Confirm correct operation. Is system operating OK?	yes / no
Condenser Manufacturer	
Condenser Model No.	
Is condenser clean and free from debris?	yes / no
Are condenser fan motors rotating correctly?	yes / no
Does store location require condenser fins to be coated?	yes / no
Does this condenser have a Variable Freq. Drive (VFD) controlling the fan motors?	yes / no
Confirm correct settings and operation of VFD.	yes / no
If no VFD, confirm correct condenser control by BAS.	yes / no
Confirm correct settings and operation of condenser split.	yes / no
Confirm correct operation of condenser drain down system.	yes / no
Is inverted trap installed on inlet side of condenser pipe work?	yes / no
Is test valve installed on inlet side of condenser pipe work?	yes / no
Record setting of liquid hold back valve.	
Is receiver level alarm device operating?	yes / no
Record level of refrigerant in tank%	
Are caps for all valves installed and tightened at end of startup?	yes / no
Record setting of rack high pressure cut out switch.	
Is sufficient oil in the oil reservoir?	yes / no
Is the oil level in each compressor correct?	yes / no
Is the oil clear in color and free of oxidation after minimum 24 runtime?	yes / no
Comments:	

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET Rack A

Store No. Loc	ation:	Store Typ	be:
	City, State		SC, SAMS, NM
Name of technician carrying of	out checks and completing th	is form	Date
All system identification label	s installed?		yes / no
All expansion valve strainers	cleaned? Check three strain	ers per rack.	yes / no
List circuit numbers of straine	ers checked.		
Are condensate drains operati	ng correctly?		yes / no
Are all glass doors adjusted p	roperly?		yes / no
Are cases shimmed every 4 fe	et?		yes / no
Are case to case joints sealed?	2		yes / no
At bottom penetrations in case	es, is foam shaved flat and se	ealed?	yes / no
System No.	Make		
Case No.	Model		
Length (feet)			
Float Circuit?			yes / no
EPR Setting	psi	Lighting Amps	
BAS Setting Cut In	°F	Fan Amps	
BAS Setting Cut Out	°F	Defrost Amps	
Superheat Setting	°F	Trim Heater Amps	
Confirm that the breakers to the Lighting Fans Defrost Trim Heaters	he following circuits are labe	eled correctly.	yes / no yes / no yes / no yes / no

System No.	Make		
Case No.	Model		
Length (feet)			
Float Circuit?			yes / no
EPR Setting	psi	Lighting Amps	
BAS Setting Cut In	°F	Fan Amps	
BAS Setting Cut Out	°F	Defrost Amps	
Superheat Setting	°F	Trim Heater Amps	
Confirm that the breakers to th Lighting Fans Defrost Trim Heaters	e following circuits are labo	eled correctly.	yes / no yes / no yes / no yes / no
System No.	Make		
Case No.	Model		
Length (feet)			
Float Circuit?			yes / no
EPR Setting	psi	Lighting Amps	
BAS Setting Cut In	°F	Fan Amps	
BAS Setting Cut Out	°F	Defrost Amps	
Superheat Setting	°F	Trim Heater Amps	
Confirm that the breakers to the Lighting Fans Defrost Trim Heaters	e following circuits are lab	eled correctly.	yes / no yes / no yes / no yes / no

REFRIGERATION INSTALLATION HANDOVER DOCUMENT / SIGN OFF SHEET Rack Data Collection for Verisae

Store No 1	Location:			Store Type:	
		City, State			SC, SAMS, NM
Project Type (circle one):		New Store	Relocation	Expansion	
Rack Letter (circle one):		A B C D E Remote Conden Remote Conden Remote Conden Remote Conden	F G ser 1 Rem ser 3 Rem ser 5 Rem ser 7	note Condenser 2 note Condenser 4 note Condenser 6	
Refrigerant Type (circle o	ne):	R22 R404A	R422D R422	A R134A R407A	Other
Full Charge		lbs	0Z.		
Charge Method (circle one	e):	Actual	Receiver Cal	culation On Site	e Measurement
Temperature (circle one):		Low	Medium		
Manufacturer (circle one):		Hill PHOENIX	Kysor Tyler	Systematic Zero Zon	e Other
Model No					
Serial No					
Rack Letter (circle one):		A B C D E Remote Conden Remote Conden Remote Conden Remote Conden	F G ser 1 Rem ser 3 Rem ser 5 Rem ser 7	note Condenser 2 note Condenser 4 note Condenser 6	
Refrigerant Type (circle o	ne):	R22 R404A	R422D R422	A R134A R407A	Other
Full Charge		lbs.	0Z.		
Charge Method (circle one	e):	Actual	Receiver Cal	culation On Site	e Measurement
Temperature (circle one):		Low	Medium		
Manufacturer (circle one):		Hill PHOENIX	KysorHussmann	Zero Zone Other	
Model No					
Serial No.					

HVAC/REFRIGERATION/EMS REQUEST FOR INFORMATION PROCESS FLOW CHART WAL-MART STORES, SUPERCENTER, SAM'S CLUB, NEIGHBORHOOD MARKET

