



STUCKEY
ARCHITECTS
Weatherford, Texas

Robert A. Stuckey
Architect

February 26, 2018

Aledo Groves; D1 Fitness Facility

ADDENDUM #2

BIDDERS ARE ADVISED OF THE FOLLOWING AND SHALL BE GOVERNED ACCORDINGLY:

Clarifications:

1. All Base Bids shall include the X-Grass Installation: Contractors may submit alternative synthetic grass product as a voluntary alternate.

Please note that the X-Grass Product shall be part of the Base Bid. The subsurface material shall be priced as a separate bid alternate: See the Revised Bid Documents.

Please reference Details 6 & 7 for 2 options on the X-Grass installation.

- a. Option #1: Detail 6 / Sheet B1.2: Set X-Grass system on a 4" concrete slab. Reinforce with #3 bars # 12" o.c.b.w.
 - b. Option #2: Detail 7 / Sheet B1.2: Set X-Grass system on a 6" crushed stone base with a 6" x 12" concrete curb with a 2x8 treated wood curb. Reinforce the curb with one (1) #3 Top & bottom.
2. Electrical panels are located on the SW corner of the building adjacent to the Fire Sprinkler Riser Room Reference the Floor Plan on A1.1. The electrical transformer is to be located due north across the paving on the NW property line corner.
 3. Revised Bid Form: Use the attached Revised Bid Form:

END OF CLARIFICATION



Robert A. Stuckey
Architect; Texas #9093
February 26, 2018